



NOTES:

1. THE MANHOLE BASE SHALL BE BEDDED ON 6" COARSE AGGREGATE. THE CONTRACTOR SHALL LEVEL AND PLUMB THE BASE PRIOR TO SETTING THE PRECAST MANHOLE RISER SECTIONS ON THE PRECAST CONCRETE BASE.
2. ALL PVC PIPES SHALL BE REMOVED FROM INVERT.
3. IF FINISHED SURFACE IS OTHER THAN IMPERVIOUS COVER IT SHALL BE 12 INCHES ABOVE GRADE.
4. SEE STANDARD DETAIL FOR BACKFILL REQUIREMENTS.



TRAVIS COUNTY WATER CONTROL AND
IMPROVEMENT DISTRICT No. 17
STANDARD DETAILS

ADOPTED:

03/01/2016

PRECAST MANHOLE ON
PRECAST BASE

THE ARCHITECT/ENGINEER ASSUMES
RESPONSIBILITY FOR APPROPRIATE
USE OF THIS STANDARD.

DETAIL NO.

WW03